

Addendum 2
July 1, 2024
South Jersey Port Corporation (SJPC)
Request for Proposals

SJPC-22-09R High Mast Tower Repairs

NOTICE

This Addendum is considered part of this Request for Proposals and must be acknowledged with your submission.

ANSWERS TO FORMALLY SUBMITTED QUESTIONS

- Q1. HMT 6 and HMT 8 require the replacement of the anchor bolt nuts. The existing leveling nuts were observed to be embedded in the concrete of the existing concrete foundation. Is there a detail or design for the removal of concrete at the top of the foundation to permit the removal of the existing nuts and the installation of the proposed new hardware?
- R1 If concrete is encountered around the nut that prevents the removal and replacement, contractor is to chip concrete out around the leveling nut as required for the removal and replacement and repair with a bonding agent and high strength non-shrink grout once the repair is completed. Submit bonding agent and high strength non-shrink grout for approval.